INTEGRA MANTLE ASSEMBLY INSTALLATION SHEET



Version 1 11/08/22 Contents of manual may be updated without notice. For the latest version of this manual please refer to our website: www.paulagnewdesigns.com.au



DESIGNS

STEP 1: Front View



STEP 2: Top View



STEP 3:



Procedure

Dismantle the screws as shown in Step 3; located on top view as shown in step 2.

Tool:

Make use of Philip head screw driver

STEP 4:



Procedure:

Mantle the Angle linear to the top of the heater unit; as shown in following steps.

Tool:

Make use of Philip head screw driver

Note: Angle Linear will be supplied with the part of heater unit.

PAUL AGNEW DESIGNS

STEP 5:



Procedure

Make sure the orientation of the angle linear as shown

STEP 6:



Front View; after assembling top angle linear

STEP 7:



Procedure:

Make sure of the clinch stud highlighted in the step 7 to align the heater unit shown in step 8.

STEP 8:



Front View; after aligning heater unit with mantle piece.

STEP 9:



Procedure:

Use Wing nut to secure the alignment in position as shown in step 9.

STEP 10:



Procedure:

Secure front Fascia panel as shown in Step 10.

STEP 11:



Procedure:

Use highlighted section in the step 11 to secure the front Fascia panel to the mantle piece.

STEP 12:



Procedure:

secure the panel using M6 screw

STEP 13:



Front view; after assembling of front fascia panel to mantle piece.

STEP 14:



Procedure:

Use the slider location in Fascia panel to assemble the Fascia grill as highlighted in step 13

PAUL AGNEW DESIGNS

STEP 13:



Procedure:

Place log ambers inside the Fascia grill as shown.

PAUL AGNEW

Integra

148 Cochranes Road Moorabbin, Victoria 3189

www.paulagnewdesigns.com.au info@paulagnewdesigns.com.au

PAUL AGNEW DESIGNS

9.